



OFFICE OF THE BLOCK DEVELOPMENT OFFICER, JALESWAR BLOCK, Dist. Balasore  
E-mail: ori-jaleswar@nic.in

### DETAILED TENDER CALL NOTICE

Advt. No. : 5268/Jaleswar, Bls. Of 2021-22.

Date: 7/10/2021.

1. The **Block Development Officer, Jaleswar Block, Balasore** on behalf of the Governor of Odisha invites **Sealed Tenders (percentage Rate)** in conformity with the DTCN, are invited from the **"D" & "C" Class Contractors** registered with State Govt. & Contractors of equivalent grade/class registered with central Govt. MES/Railways for Execution of **Civil Works for Total Three Nos. Of works from Rs. 19.13 Lakhs to Rs. 19.97 Lakhs** per unit of work under Panchayat Samiti, Jaleswar, Balasore. The Tender Documents (**DTCN & BOQ**) and Detailed List of works mentioned in **Annexure-A** can be obtained from District **NIC Website ([www.baleswar.nic.in](http://www.baleswar.nic.in))** from **Dated: 08.10.2021 to 24.10.2021** till 5PM.
2. The Tender documents (**DTCN & BOQ.**) duly signed by the contractors should be accompanied with the self attested photo copy of **Valid Registration Certificate (Contractor Licence), Valid GST Registration Certificate and PAN Card**. The tender must be accompanied with **AFFIDAVIT** regarding authentication of Documents and Credentials.
3. The Tender documents (**DTCN & BOQ.**) Should be accompanied with requisite **Tender paper Cost (Non Refundable)** in shape of **Bank Demand Draft** drawn in favour of **Block Development Officer, Jaleswar Block, payable at Jaleswar**, from any Nationalised Bank. The Cost of the Tender paper mentioned against the each works.
4. The Sealed Tender Paper will be addressed to The **BDO, Jaleswar Block, Dist. Balasore** and will be Received up to date : **28.10.2021** till 5P.M. through **Speed post/Registered post/Courier only**. The tender must be subscribed the name of the work on top of the sealed envelope.
5. The tenders are scheduled to be opened on **Dated: 29.10.2021 at 11.30 A.M.** at the Office of **BDO, Jaleswar Block, Dist. Balasore**, in presence of the Tenderers or their authorised representatives. No adjustment of Tender per Cost (Non-refundable) will be entertained in any manner.
6. The detailed Terms and conditioned List of works (DTCN and BOQ) can be downloaded at District **NIC Website ([www.baleswar.nic.in](http://www.baleswar.nic.in))**.
7. The incomplete bid in any form will be liable for rejection. The undersigned reserve and the right to cancel the tender without assigning any reason thereof.

07/10/21

**Asst. Engineer (NHM)**  
**DRDA, Balasore**

BDO, Jaleswar Block.



OFFICE OF THE BLOCK DEVELOPMENT OFFICER, JALESWAR BLOCK, Dist.Balasore  
E-mail: ori-jaleswar@nic.in

**Detailed Tender Call Notice 2021-22 ( Annexure-A)**

Sl. No.	Name of the Work	Estimated Cost (in Rs.) Without GST.	Cost of Tender Paper (in Rs.)	Period of Completion & Class of Contractor	Availability of Tender Documents (DTCN&BOQ)
1	2	3	5	6	7
1	Construction Of New Sub Centre Building at Chafra under Jaleswar Block for the year of 2021-22.	19,96,673.00	6000.00	04 Months ("D" & "C")	The Tender Documents (DTCN&BOQ) may be obtained from NIC website ( <a href="http://www.baleswar.nic.in">www.baleswar.nic.in</a> ) from 08.10.2021 to 24.10.2021.
2	Construction Of New Sub Centre Building at Rai RamchandraPur under Jaleswar Block for the year of 2021-22.	19,96,715.00	6000.00	04 Months ("D" & "C")	
3	Construction Of New Sub Centre Building at Shyamnagar under Jaleswar Block for the year of 2021-22.	19,13,156.00	6000.00	04 Months ("D" & "C")	

MA  
07/10/21

Asst. Engineer (M&E)  
PADA, Balasore

BDO, Jaleswar Block,  
Balasore



OFFICE OF THE BLOCK DEVELOPMENT OFFICER, JALESWAR BLOCK, Dist. Balasore  
E-mail: ori-Jaleswar@nic.in

**PANCHAYAT SAMITI, JALESWAR BLOCK  
DIST. BALASORE**

**DETAILED TENDER CALL NOTICE FOR BUILDING WORKS**

**NAME OF THE WORK:- 1. Construction of New Sub Centre Building at \_\_\_\_\_  
under Jaleswar Block in the District of Balasore.**

**ESTIMATED COST: - Rs. \_\_\_\_\_ (Fill up the place and cost by the agency as per Annexure-A)**

1. Sealed tenders are invited from the registered "D"&"C" Class contractor of P.W.D. / C.P.W.D./ M.E.S. / Railway in prescribed form to be eventually drawn in P.W.D. Form P-1 and will be received by The Office of the BDO, Jaleswar Block, Dist. Balasore , Date : **28/10 /2021 up to 5 pm.** for the works and will be opened by the BDO, Jaleswar Block, Dist. Balasore in the presence of the tenderers or their authorized agents at **11.30 A.M. on Date : 29 /10/2021.**
2. The tenderers should please note that the work will have to be completed within **04 (Four) Months** commencing from the date of issue of work order for the works as mentioned in **Annexure-A.**
3. The Successful bidders will required to pay Earnest Money Deposit and Initial Security Deposit of total **2% (Two Percent)** of estimated amount in shape of **NSC/POTD/KVP/POSB/Fixed Deposit** duly pledged to BDO, Jaleswar Block, Dist. Balasore, otherwise their tender will not be considered, as per the term and conditions laid down in O.P.W.D. code.
4. a) The plan & specifications for the work can be seen at Civil Engineering Section(NHM, Bls.) during working hours and days. Complaints at a future date that the plan and specifications have not been seen can not be entertained. The Contractor may obtain a set of tender documents with DTCN and detail list of the works by down load from district web site [www.baleswar.nic.in](http://www.baleswar.nic.in), on **08/10/2021 to 24/10/2021 up to 5P.M.**  
b) The **amount of tender paper cost** (Non refundable) mentioned in list to be attached with the tender schedule in shape of **Bank Draft** in the name of **BDO, Jaleswar Block, payable at Jaleswar** in any nationalized bank, this amount is not refundable. Tender must be submitted in a sealed cover. The name of the work is to be noted on the cover. Without cost of the tender paper the tender will be rejected.  
c) All other information's can be obtained on application to the BDO, Jaleswar Block, dist. Balasore.

**Assistant Engineer (NHM)  
ORDA, Balasore**

Signature of the Contractor

**BDO, JALESWAR BLOCK**



OFFICE OF THE BLOCK DEVELOPMENT OFFICER, JALESWAR BLOCK, Dist. Balasore  
E-mail: ori-Jaleswar@nic.in

- d) Any tender received after the schedule date and time will be rejected by this office. As such the contractors can not claim his/her bidder ship merely in the ground of submission of tender from tenderer. This Office will not be liable responsible if there is any delay in receipt of tender documents, the intending contractors sent through registered post/ Speed post/ Courier the tender documents sent by the intending contractor through registered post do not reach in Office within the schedule of date and time. Their offers will not be considered on any account even if the tender documents were dispatched by the tenderers before due date.
5. The BDO, Jaleswar Block, Dist. Balasore, reserves the right to reject any or all the tenders received without assigning any reasons thereof.
6. The bidder whose tender will selected for acceptance shall within a period of seven days upon written intimation being given to him of acceptance of his tender make an security deposit of **2% (Two Percent)** of Estimated Cost. So that the total Security deposit will be total **2% (Two Percent)** of the tendered amount as shown in clause 3 above and sign the agreement in the P.W.D. Form No. P-1 ( Schedule XLV No. 61) for the fulfillment of the contract in the office of the BDO, JALESWAR BLOCK, Dist. Balasore.

The security deposit, together with the earnest money and the amount with – held according to the provisions of P-1 agreement shall be retained as security deposit for the due fulfillment of this contract. Failure to enter into the required agreement and to make the security deposit as above shall entail forfeiture of the earnest money.

No tenderer shall be finally accepted without , the required amount or security money being deposited. The written agreement to be entered into between the Contractor and Government shall be the foundation of rights of the parties and the contract shall be deemed to be incomplete until the agreement has first been signed by the contractor and then by the proper officers authorized to enter into the contract on behalf of the Govt. The department will accept the security deposit in the form of **NSC/POTD/KVP/POSB/Fixed Deposit** duly pledged to the BDO, JALESWAR BLOCK, Dist. Balasore and in no other form. The acceptance of less quoted rates of tenderer to be deposited differential amounts from the estimated amounts during the agreement period in shape of as mentioned above as for ISD.

7. The Percentage rates of schedule of Less should be quoted in words and figures in percentage basis at the end of the BOQ mentioned and the excess percentage rates will not be accepted and this will consider for schedule of rates for execution of the agreement if this will found lowest. Otherwise the tender will be liable for rejection. In case of discrepancies between words and figures. The words shall prevail. The tender shall be written legibly and free from erasures, overwriting or correction of figures, Correction, where unavoidable should be made by scoring out, initialling, dating and rewriting.

Signature of the Contractor

  
Asst. Engineer (NH&I),  
DRDA, Balasore.


  
BDO, JALESWAR BLOCK.



OFFICE OF THE BLOCK DEVELOPMENT OFFICER, JALESWAR BLOCK, Dist. Balasore  
E-mail: ori-Jaleswar@nic.in

8. The contractors will be responsible for payment of all royalties or other charges for quarrying materials. All local taxes inclusive of State Sales tax, GST & Income Tax, Ferry and Tollage charges are to be paid by the Contractor.
9. The tender may not, at the discretion of the competent authority be considered unless accompanied by self attested copies of GST Registration Certificate, PAN and Contractor Licence / Registration Certificate and Affidavit for authentication of documents as the case may be and the original certificate/ documents to be produced before the BDO, JALESWAR BLOCK, Balasore at the time of opening of the tender/ drawl of agreement.
10. The contractor shall be fully liable to indemnify the department for payment of any compensation under 'workman' compensation Act VII of 1923, on account of the workmen being employed by him and the full amount of compensation paid will be recovered from the contractor.
11. Every tenderer must examine the detailed specification of Orissa before submitting his tender. This right is reserved without impairing the contract to make such increase or decrease in the quantities or items of work mentioned in the schedule attached to the tender notice as may be considered necessary to complete the work fully and satisfactorily. Such increase or decrease shall in no case invalidate the contractor's rates. It shall be definitely understood that the Government do not accept any responsibility for the correctness of the quantities shown in the schedule. The schedule is liable to alteration by omission, or additions or deductions & it shall in no case invalidate the contract and no extra monetary compensation will be entertained.
12. All reinforced cement concrete work should confirm to Orissa Detailed Standard Specification & should be of M20(1:1.5:3) having minimum compressive strength in work test of 200 kg Cm<sup>2</sup> in 15 Cm. Cubes at 28 days after mixing and tests conducted in accordance with I.S.- 456 and 516 using 12 mm, to 20 mm. Size hard black broken granite chips ( 20mm size not to exceed 25% ).
13. Shuttering and centering shall be with seasoned Non-sal wood planks and the inside of which shall be lined with suitable sheeting and made leak proof and water tight or alternatively steel shuttering and centring may be used.
14. The contractor shall make all arrangements for proper storage of materials, but no cost for raising shed for the storage of materials and pay of watchmen etc will be borne by the Department. These are also to be borne by the contractor. The Department is not responsible for considering the theft of materials at site. It is contractor's risk. Under any such plea if the contractor stops the work, he shall have to pay the full penalty as per clauses of the P-1 contract.

Signature of the Contractor

  
Asst. Engineer (M. & E.)  
OADA, Balasore

  
BDO, JALESWAR BLOCK.



OFFICE OF THE BLOCK DEVELOPMENT OFFICER, JALESWAR BLOCK, Dist.Balasore

E-mail: ori-Jaleswar@nic.in

15. For the purpose of jurisdiction in the event of dispute if any contract should be deemed to have entered into within the State of Odisha and it is agreed that neither party to the contract nor the agreement will be competent to bring a suit in regard to the matters covered by this contract at any place outside the state of Odisha.
16. After the work is finished all surplus materials and debris are to be removed by the contractor and preliminary work such as vats, mixing platform etc. are to be dismantled and all the materials are to be removed from the site. The ground up to 30m. (100') wide from the building should be cleared and dressed. No extra payment will be made to the contractor on this account The rate quoted should be inclusive of all these items.
17. The contractor shall not interfere with the execution of water supply or electrical fittings arrangement and any other works entrusted to any other agency by the department at any time during the progress of the work.
18. The department will have the right to inspect the scaffolding and centering made for the work and can reject partly or fully such structures if found defective in their opinion.
19. The contractor will have to arrange for water supply for all works and make sanitary arrangements for night work whenever necessary at his own cost.
20. Bailing out of water from the foundation either rain water or subsoil water if necessary should be borne by the contractor, No payment will be made for bench marks. Level pillars, profiles and benching and leveling ground where required. The rates quoted should be for finished items of work inclusive of these incidental of work.
21. All the quantities mentioned in the schedule are combined for ground floor and multi floors, in case of multistoried buildings the rates should be through for the same.
22. Cement concrete in roof slab, beams etc. whenever prescribed by the Engineer-in-charge shall be machine mixed and vibrated and the contractor should arrange his own mixers, concrete vibrators, pumps etc. for the purpose.
23. It should be understood clearly that no claims, what – so – ever will be entertained in regard to extra items of works of extra quantity of any items besides estimated amount. A written order must be obtained from the BDO, JALESWAR BLOCK. Balasore and rates settled for the extra items of works or extra quantity of any item of work according to clause 11 of P-1 contract. The rates for any time not covered in the Agreement will be arrived on derivation from the rate of same class of item of work with any different specification provided in the agreement with addition or subtraction of corresponding cost of materials. In case, rate can not be derived from the agreement the same will be arrived or derived from the schedule of rates in vogue at the time of actual execution of that item of work.

Signature of the Contractor

  
Asst. Engineer (NHM)  
DRDA, Balasore

  
BDO, JALESWAR, BLOCK.



OFFICE OF THE BLOCK DEVELOPMENT OFFICER, JALESWAR BLOCK, Dist. Balasore  
E-mail: ori-jaleswar@nic.in

24. The tenderer shall have to abide by the C.P.W.D. Safety code rule introduced by the Government of India Ministry of works, Housing and Supply in their standing orders No. 44 to 50 dated 25.11.57.
25. Tenderers are required to abide by the fair wage clause as introduced by the Government of Orissa, works Department No. CA VIIIIR, 18/52-55 dt. 26.2.55 and No. IIM 56/6-28842 dt. 27.9.61 in case of any complaint by the labourers working about the non-payment of less payment of his wages as per minimum wages act. The BDO, JALESWAR BLOCK., Balasore will have the right to investigate and if contractor is found to be in default, he may recover such amount from the dues of the contractor and pay the due amount to such labour directly under intimation to the local labour officer and the Government and the decision of the BDO, JALESWAR BLOCK., Balasore will be final and binding on the Contractor.
26. The contractor will be responsible for the loss or damage of any departmental materials/equipment's clause 13/30 during execution of the work due to reasons what- so - ever and the cost of such materials will be recovered from him at the market rates whichever is higher.
27. The contractor should arrange at his own cost necessary tools and plants, machines, concrete Mixer & vibrators and other machineries such as pumps etc. required for the execution of the work and the rates quoted should be inclusive of the running charges of such plants and cost of consumables.
28. The tenderers are required to go through each clause of P.W.D., From No. P-1 carefully in addition to clause mentioned herewith before tendering.
29. No part of the contract shall be sub-let without written permission of the BDO, JALESWAR BLOCK., Balasore or transfer made by power of attorney to others to receive payment on contractor's behalf.
30. If further necessary information is required, the BDO, JALESWAR BLOCK., Balasore will furnish such, but it must be clearly understood that the tenders must be received in order and according to instructions.
31. Cement shall be used in bags and weight of one cubic meter of cement being taken at 41, 42 quintals.
32. No contractor will be permitted to furnish their tenders in their own manuscript papers.
33. Every tenderer is expected before quoting his rates to inspect the site of proposed work. He should also inspect the quarries and satisfy himself about the quality. Availability of materials medical aids, labour and food stuffs etc, and the rates should be inclusive of all those items of work. In every case the materials must comply with the relevant specifications and samples of stones, metals, chips etc for approval of the Engineer- in- Charge/ BDO, JALESWAR BLOCK., Balasore.
34. Government will not however after acceptance of contract rate pay any extra charge for lead or any other reasons in case the contractor is found later on to have misjudged the materials available.

Signature of the Contractor

  
Asst. Engineer (NMM)  
DRDA, Balasore

  
BDO, JALESWAR BLOCK.



OFFICE OF THE BLOCK DEVELOPMENT OFFICER, JALESWAR BLOCK, Dist.Balasure  
E-mail: ori-Jaleswar@nic.in

35. All fittings for doors and windows if supplied by the Contractor should be of best quality and should be approved by the Engineer –in-charge / BDO,JALESWAR BLOCK., Balasure.
36. The tender's containing extraneous conditions not covered by the tender call notice are liable for rejection.
37. All the tenders received will remain valid for a period of fifteen days from the date of receipt of tenders. The period of validity can also be extended if agreed to by the Department and the contractor.
38. Letters ect. found in the tender box raising or lowering rates or dealing with any point in connection with the tender will not be considered.
39. All reinforced cement concrete works in lintels, columns, beams, chajja, roof slab and other such works should be finished smooth and no extra charges for plastering if required by the department.
40. The tenderer shall bear cost of various incidental sundries and contingencies necessitated by the work falling within the following similar categories.
  - a). Rent, royalties and other charges of materials octroi duties all other taxes including sales tax, ferry/tools conveyance charge and other cost on account of land and building including temporary building required by the tenderer for collection of materials storage housing of staff or other by the tenderer for purpose of work . No rent will however be payable to Government for temporary occupation of land owned by Government at the site of the work.
  - b). Labourers camp or huts necessary to a suitable scale including conservancy and sanitary arrangements therein to the satisfaction of the local health authorities.
  - c). Suitable water supply including pipe water supply when ever available for the staff and the labour as well as for the work.
  - d). Fees and duties levied by the Municipal Canal or Water supply authorities.
  - e). Suitable equipments and wearing apparatus for labour engaged in risky operations.
  - f). Suitable fencing, barriers, signals including paraffin and electric signals where necessary at works and approaches in order to protect the public and employee from accidents.
  - g). Compensation including cost of any suit for injury persons or property due to neglect of any major precautions and also sums which may become payable due to operation of Workmen's Compensation Act.

Signature of the Contractor

*M. K. S. S. S.*  
Asst. Engineer (MMS)  
BRDA, Balasore

*[Signature]*  
BDO, JALESWAR BLOCK.



OFFICE OF THE BLOCK DEVELOPMENT OFFICER, JALESWAR BLOCK, Dist.Balasore  
E-mail: ori-Jaleswar@nic.in

- h). The contractor has to arrange adequate lighting arrangements for night work however necessary at his own cost.
- i). The contractor has to arrange all the building materials including equipments required for undertaking under reamed piles foundation for starting the work.
41. 3% (Three percent) of gross amount of the bill will be deducted towards income tax from the contractor's bills.
42. Where it will be found necessary by the department, the Officer-in-charge of the work shall issue an order book to the contractor to be kept at the site of the work with pages serially numbered order regarding the work whenever necessary are to be entered in this book by the BDO, JALESWAR BLOCK., Balasore/Engineer- in charge of work with their dated signature and duly noted by the contractor or his authorized agent, with their dated signatures. Order entered in this book and noted by the contractor's agent shall be considered to have been duly given to the contractor for following the instructions of the department. The order book shall not be removed from the site of work with out permission of the BDO, JALESWAR BLOCK., Balasore and to be submitted the Engineer-in-charge / BDO, JALESWAR BLOCK., Balasore every month.
43. Over and above to these conditions the terms and conditions and rules and regulations as laid down or Detailed Standard Specifications of Odisha P.W.D. Code are also binding.
44. Under no circumstance interest is chargeable for the dues or additional dues, if any payable for the work.
45. Item where rates quoted by the tenderers are less than 15% below the current schedule or rates / estimated rates the differential cost between estimated amount and the tender amount shall be withheld till the completion of such items having low rates.
46. The date of issue of the notice to the contractor to attended of the office BDO, JALESWAR BLOCK., Balasore for signing the agreement shall be treated as the date of commencement of work.
47. In the percentage rate tenders, only percentage quoted shall be considered. Percentage quoted by the tender shall be accurately filled in figures and words, so that there is no discrepancy. If any discrepancy is found in the percentage quoted in words and figures, then the percentage quoted by the tenderer in words shall be taken as correct. If any discrepancy is found in the percentage quoted in percentage excess/less and total rate quoted by the tenderer, then percentage will be taken as correct.

Signature of the Contractor

  
Aml. Engineer (P.W.D.)  
BDO, JALESWAR BLOCK.

  
BDO, JALESWAR BLOCK.



OFFICE OF THE BLOCK DEVELOPMENT OFFICER, JALESWAR BLOCK, Dist.Balasore  
E-mail: ori-Jaleswar@nic.in

The percentage rate quoted in the tender without mentioning excess or less and not supported with the corresponding amount will be treated as excess. The tenderer will write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points, the first decimal point shall only be considered without rounding off. Where the tenderer has omitted to quote the percentage rates either in figure and words, the Officer opening the tender should record the omission.

**48. Security for Performance:**

The successful bidder has to deposit initial security @ 2% of the bid value which includes EMD. The security deposit so deposited shall be returned to the contractor after the defect liability period (one year) is over and subject to the Certificates that no liability attached to contractor subject to payment of final bill.

**49. Evaluation of Tenders:**

The tenders will be verified for accuracy in the numerical calculations. Any tender with arithmetical mistakes will be corrected on the basis of the quantities of work given in the tender form and percentage rate quoted by the tenderer.

In case of tenders where the percentage rate increase or decrease and the price appears unrealistic, such tenders will be considered as unbalanced & In case the tenderer is unable to provide satisfactory explanations, the authority reserves the right to disqualify such tenders.

**50. Successful Tender:**

The work will be awarded to the most suitable and responsive tenderer. The tenderer whose tender is accepted shall forth with upon intimation given to him in writing about acceptance of his tender makes an initial security deposit as will be intimated within 7 days of such intimation and sign the agreement on PWD form No. P1 for the due fulfilment of the contract in Office of the Block Development officer Jaleswar.

In case failure by the contractor to deposit ISD or to enter into the agreement, the EMD for the tender will be forfeited.

**51. Jurisdiction of Court :**

That for the purpose of jurisdiction in the event of dispute if and the contract should be deemed to have been entered in to within the State of Odisha and it is agreed that neither party to the contract or agreement will be competent to bring a suit in regard to the matters covered by the contract at any place outside the State of Odisha,

Signature of the Contractor

Asst. Engineer (NHM)  
DRDA, Balasore

BDO, JALESWAR BLOCK.



OFFICE OF THE BLOCK DEVELOPMENT OFFICER, JALESWAR BLOCK, Dist.Balasore  
E-mail: ori-Jaleswar@nic.in

52. Subletting of the Contract:

The contractor shall not without the written consent of the Engineer-in-Charge sub-let full or any portion of the contract. Any sub letting shall in no way absolve the contractor of any of his responsibilities under this contract.

53. Extension of Time:

Time shall be considered as the essence of the contract . The period of completion is fixed and cannot be altered except in case of exceptional circumstances with due approval of next higher authority.

The contractor shall request such extension of time within one month the expiry of the contract period.

54. If the rate quoted by the bidder is less than 15% of the tendered amount, then such a bid shall be rejected and the tender shall be finalized basing on merits of rest bids. But, if more than one bid is quoted at 14.99% (Decimals up to two nos will be taken for all practical purposes) less than the estimated cost, the tender accepting authority will finalize the tender through a transparent lottery system, where all bidders/ their authorized representatives, the concerned Officer and .A.O will remain present.

55. Land required for storage of materials will be arranged by the contractor at his own cost and responsibility if departmental land is not available.

56. Additional performance security shall be obtained from the successful bidder when the Bid amount is less than the estimated cost put to tender. In such an event, the bidders who have quoted less Bid price/rates than the estimated cost put tender shall have to furnish the amount of differential cost i.e. estimated cost put to tender minus the quoted amount as additional performance security as per revised norms, in shape of post office savings bank account / National Savings Certificate / Post Office time deposit Account / Kissan Vikas Patra/ Deposit Receipt of Schedule Bank duly pledged in favour of the Block Development officer ,Jaleswar, failing which the tender in his favour shall be liable for rejection.

Signature of the Contractor

  
Asst. Engineer (NHM)  
URDA, Balasore

  
BDO, JALESWAR BLOCK.

**BILL OF QUANTITIES SI. No. -01**

Name of the work	: Construction of Sub-center at Chafila under Jaleswar block for the year 2021-22.
Approx. Estimated Cost	: -Rs. 1996673.00
E.M.D. to be deposited	: - Not Required
Cost of Tender Paper	: - Rs. 6,000/-
Class of Contractor	: - 'D' & 'C' Class
Last Date of Avail the tender Paper in Web site	: - 24.10.2021
Last Date of receipt of tender	: - 28.10.2021
Date of Opening of Tender	: - 29.10.2021 at 11.30 A.M.
Time of Completion	: - Four Months

Sl. No.	DESCRIPTION OF ITEMS	Quantity	Unit	Rate in Figure	Amount
1	Earth work in foundation of hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge.	74.45	Cum	184.60	13743.47
2	Filling foundation and plinth with sand well watered and rammed including cost, conveyance of materials, labour T&P, royalty etc. complete as per direction of the Engineer-in-charge.	173.32	Cum	351.70	60956.64
3	Providing P.C.C. (1:4:8) with PSC cement & 4cm size h.g. metal of approved quality in foundation / floor including hoisting laying concrete, cost & conveyance of materials, labour ,T&P, royalty, taxes, curing etc. complete as per direction of the Engineer-in-charge.	25.86	Cum	4827.50	124839.15
4	Providing Reinforced Cement concrete (1:2:4) with PSC cement & 12mm size H.G.chip of approved quality from approved quarry including hoisting laying concrete with cost conveyance & materials royalty,taxes,labour,T&P required for the work watering & curing for specified period complete as per direction of the Engineer-in-charge.	3.11	Cum	6797.70	21140.85
5	Providing R.C.C. M-20 Grade in Foundation/ Super-Structure having a minimum compressive strength( In work test)250 Kg./ cm 2 in 15 cm. cubes at 28 days curing after mixing and test conducted in accordance with I.S. 456 and I.S. 516 using PSC cement & 10mm. To 20mm. Size black hard crusher broken granite stone chips of approved quality and from approved Quarry including hoisting to required height lowering laying position and compacting concrete by appropriate vibrators and watering and curing for 28 days including cost of rigid smooth steel centering shuttering and finishing the exposed surface as directed including cost conveyance, royalties and taxes of all materials and cost of all labour, T&P required for the concrete etc complete in all respect but excluding cost of M.S.Rods or Tor steel etc, complete as per specification & direction Engineer-in-charge. (i) RCC in Foundation	8.20	Cum	5547.70	45491.14
5.1	RCC in plinth beam/ Grade beam	4.72	Cum	5922.40	27953.73

  
**Asst. Engineer (NHM)**  
**DRDA, Balasore**

BOQ-01/01

5.2	RCC in Column beam	8.97	Cum	11304.10	101397.78
5.3	RCC in Lintel	1.64	Cum	9223.30	15126.21
5.4	RCC in Chajja/ Shelves	2.750	Cum	12455.50	34252.63
5.5	RCC in roof slab	9.66	Cum	9804.90	94715.33
6	Providing & fixing in position High yield deformed bars/ reinforcement conforming to Fe 500 grade of SAIL make with cutting, bending, binding, straightening, tying and placing in position, using binding wire 18 to 20 gauge, cost & conveyance of materials,labour, T &P etc. complete as per direction of the Engineer-in-charge.	41.37	Qtl	8221.40	340119.32
7	Providing Fly ash brick masonry in C.M.(1:6) with fly ash brick & PSC cement of approved quality and size including splays, cutting, circular moulding with cost & conveyance of materials, labour ,T&P, royalty, taxes, curing etc. complete as per direction of the Engineer-in-charge. <b>(i) In foundation &amp; Plinth</b>	50.12	Cum	4334.70	217255.16
	<b>(ii) Superstructure</b>	39.78	Cum	4368.00	173759.04
8	Providing 12mm thick cement plaster in c.m. (1:6) over brick work finished smooth with PSC cement including cost & conveyance of materials, labour, T&P, royalty, taxes, curing etc. complete as per direction of the Engineer-in-charge.	312.43	Sqm	137.50	42959.13
9	Providing 16mm thick C.P. in C.M.(1:6) over brick work finished smooth after racking out joints with using PSC cement & cost, conveyance of materials labour, T&P required for the work including royalty etc.complete as per direction of the Engineer-in-charge.	161.40	Sqm	195.70	31585.98
10	Providing 6mm thick C.P. in C.M.(1:4) to R.C.C surface including close deep chipping & slurry treatment with PSC cement & cost, conveyance of materials labour, T&P required for the work including royalty etc.complete as per direction of the Engineer-in- charge.	63.58	Sqm	154.50	9823.11
11	Providing 12mm thick plaster in c.m. (1:4) for skirting and dados using PSC cement including cost & conveyance of materials, labour, T&P, royalty, taxes, curing etc. complete as per direction of the Engineer-in-charge.	41.69	Sqm	159.30	6641.22
12	Supplying, fitting and fixing vetrified tile in floors of size 600mm x 600mm of approved make with application of polymer modified cement based water resistant adhesive bed of required thickness of 10mm and filling joints with epoxy grout of approved quality including cost of all materials, labour T&P etc required for the work complete as per direction of the Engineer-in-Charge	101.88	Sqm	1016.20	103530.46
13	Providing & fixing Glazed Ceramic tiles (30cmx20cm) conforming to IS 13753 in walls, risers, dado, skirting treads on 12mm thick bed of cement mortar 1:3 (1cement : 3sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost & conveyance of materials,royalty labour, T &P etc. complete as per direction of the Engineer-in-charge.	125.35	Sqm	1131.10	141783.39

  
 Asst. Engineer (NHM)  
 DRDA, Balaasore

BOQ-01/02


14	Fixing Granite tiles (supplied) in walls, risers, dado, skirting on 12mm thick bed of cement mortar 1:3 (1cement : 3sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including cost & conveyance of materials, royalty, labour, T & P etc. complete as per direction of the Engineer-in-charge.	2.68	Sqm	2956.80	7924.22
15	Supplying, fitting & fixing dressed seasoned Sal wood work framed and fixed (wrought and put up) in trusses, purlin, frames of door, windows, ventilators & beams including tarring 1 coat to back.	0.51	Cum	51783.4	26409.53
16	Supplying & fixing W.I. Clamps 25cm to 30cm long of 35mm x 5 mm size for doors & windows and ventilators including fixing in cement concrete (1:3:6) with 12 mm to 20 mm hard stone chips or in cement mortar (1:3) including cost of materials	60	Nos	11.3	678.00
17	Supply & fixing 32 mm thick Piasal wood panel door / window shutter with 20mm to 25mm thick panel plank complete with wooden hinged cleats etc. including all labour charges but excluding the cost of fittings.	18.29	Sqm	4287.5	78418.38
18	Providing & fixing M.S. Iron shutters for Doors/ Window made up of M.S angle frame, M.S Sheet, M.S flat including cost & conveyance of all materials, fitting, labour, T&P required for the work etc. complete as per direction of the Engineer-in-charge.	504.00	Kg	143.50	72324.00
19	Supply & fixing of M.S. widow grill door & grills including cost of screws complete including cost & conveyance of all materials, fitting, labour, T&P required for the work etc. complete as per direction of the Engineer-in-charge.	605.75	Kg	88.90	53851.18
20	Providing three coats of white washing with shell lime including necessary preparation of surface, cost & conveyance of materials, labour, T&P etc. complete as per direction of the Engineer-in-charge.	32.79	Sqm	15.80	518.08
21	Providing two coats of distemper of approved shade over one coat of primer on wall surface including cost, conveyance of materials labour, T&P etc. complete as per direction of the Engineer-in-charge.	258.48	Sqm	129.00	33343.92
22	Finishing wall surface of wall with cement base wall putty & finished smooth to receive pain including cost, conveyance of materials labour, T&P etc. complete as per direction of the Engineer-in-charge.	258.48	Sqm	71.80	18558.86
23	Earth work in hard soil beyond initial lead & lift & carriage Earth by Mechanical Means including dressing, breaking clods to maximum 5cm to 7cm, laying in layers not exceeding 0.3 m in depth including sectioning, cambering & ordinary compaction of PRR & all labour, T&P, royalty & taxes etc. complete as per direction of the Engineer-in-charge.	65.32	Cum	339.50	22176.14
24	Providing 2.5cm thick Damp proof course with P.C.C (1:2:4) using 12mm size h.g chips including cost & conveyance of materials, labour, T&P royalty tax, curing etc. complete as per direction of the Engineer-in-charge.	17.03	Sqm	298.10	5076.64
25	Providing 20mm thick grading plaster ( 1:4) over the roof slab as grading plaster finished smooth using PSC cement including watering curing for specified period with cost conveyance, royalty & taxes of all materials, labour, T&P, scaffolding etc. complete as per specification & direction of Engineer-in charge.	96.03	Sqm	219.20	21049.78

  
 Asst. Engineer (NHM)  
 BKDA, Dabhoi

BOQ-01/03

26	2 coats of synthetic enamel paint on new / old steel surface with one coat primer in ground floor etc. complete as per direction of the Engineer-in-Charge.	38.67	Sqm	194.70	7529.05
27	2 coats of synthetic enamel paint on new / old wood surface with one coat primer in ground floor etc. complete as per direction of the Engineer-in-Charge.	47.19	Sqm	198.90	9386.09
28	S & F 4 mm plain glass with cost of nail , screw for ventilater including necessary preparation of surface, cost & conveyance of materials, labour, T&P etc. complete as per direction of the Engineer-in-charge.	1.49	Sqm	509.00	758.41
29	Providing two coats of water proofing cement paint including necessary preparation of surface, cost & conveyance of materials, labour, T&P etc. complete as per direction of the Engineer-in-charge.	224.97	Sqm	50.90	11450.97
30	Supply of 100 mm Mild steel butt hinges including necessary screws.	24	Nos	19.1	458.40
31	Supply of 250 mm x 16 mm Aluminium Sliding door bolt including necessary screws.	10	Nos	229.7	2297.00
32	Supply of 150 mm Aluminium handle with 175mm x 40 mm flat including necessary screws.	20	Nos	32.2	644.00
33	Supply of 150 mm x 10 mm Aluminium tower bolt including necessary screws.	10	Nos	52.8	528.00
34	Supply of 200 mm x 10 mm Aluminium tower bolt including necessary screws.	10	Nos	64.1	641.00
35	Moorum filling & consolidated with hand ramming etc. complete as directed by the Engineer in charge .	7.36		1259.9	9272.86
36	S&F masonry informatory sign board including painting, lettering as per drawing etc. complete as directed by the Engineer in charge .	1	Nos	6304.8	6304.80
				<b>Total : Rs.</b>	<b>1996673.04</b>
	<b>Total : 36 (Thirty Six items ) only</b>			<b>Say :- Rs.</b>	<b>1996673.00</b>

Signature of Contractor

  
Asst. Engineer (NHM),  
DRDA, Balasore

  
B.D.O. , Galeswar Block

My/ our quoted rate is..... % Excess over / Less than / equal to  
the estimated cost.

(Rate to be quoted both figure & word)

Submission of Rs. 6,000 /- (Rupees Six Thousands ) Only, Vide Bank Draft No.

Dated. , Name of the Bank towards cost of the tender paper .

Signature of Contractor

  
B.D.O. , Galeswar Block

BOQ-01/04

**BILL OF QUANTITIES SI. No. -02**

Name of the work **Construction of Sub-center at R.R. Pur under Jaleswar block for the year 2021-22.**

Tender Call Notice No

Approx. Estimated Cost :-Rs. 1996715.00

E.M.D. to be deposited :- Not Required

Cost of Tender Paper :- Rs. 6,000/-

Class of Contractor :- 'D' & 'C' Class

Last Date of Avail the tender Paper in Web site :- 24.10.2021

Last Date of receipt of tender :- 28.10.2021

Date of Opening of Tender :- 29.10.2021 at 11.30 A.M.

Time of Completion :- Four Months

Sl. No.	DESCRIPTION OF ITEMS	Quantity	Unit	Rate in Figure	Amount
1	Earth work in foundation of hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge.	74.45	Cum	184.60	13743.47
2	Filling foundation and plinth with sand well watered and rammed including cost, conveyance of materials, labour T&P, royalty etc. complete as per direction of the Engineer-in-charge.	139.33	Cum	374.00	52109.42
3	Providing P.C.C. (1:4:8) with PSC cement & 4cm size h.g. metal of approved quality in foundation / floor including hoisting laying concrete, cost & conveyance of materials, labour ,T&P, royalty, taxes, curing etc. complete as per direction of the Engineer-in-charge.	20.91	Cum	4633.30	96882.30
4	Providing Reinforced Cement concrete (1:2:4) with PSC cement & 12mm size H.G.chip of approved quality from approved quarry including hoisting laying concrete with cost conveyance & materials royalty,taxes,labour,T&P required for the work watering & curing for specified period complete as per direction of the Engineer-in-charge.	3.11	Cum	6560.80	20404.09
5	Providing R.C.C. M-20 Grade in Foundation/ Super-Structure having a minimum compressive strength( In work test)250 Kg./cm 2 in 15 cm. cubes at 28 days curing after mixing and test conducted in accrdance with I.S. 456 and I.S. 516 using PSC cement & 10mm. To 20mm. Size black hard crusher broken granite stone chips of approved quality and from approved Quarry including hoisting to required height lowering laying position and compacting concrete by appropriate vibretors and watering and curing for 28 days including cost of rigid smooth steel centering shuttering and finishinf the exposed surface as directed including cost conveyance, royalties and taxes of all materials and cost of all labour, T&P required for the concrete etc complete in all respect but excluding cost of M.S.Rods or Tor steel etc, complete as per.specification & direction Engineer-in-charge. (i) RCC in Foundation.	8.20	Cum	5302.70	43482.14

  
Asst. Engineer (NHM)  
DRDA, Balasore


BOA-02/01

5.1	RCC in plinth beam/ Grade beam	4.72	Cum	5674.30	26782.70
5.2	RCC in Column Beam	8.97	Cum	11037.90	99009.96
5.3	RCC in Lintel	1.64	Cum	8947.20	14673.41
5.4	RCC in Chajja/ Shelves	2.750	Cum	12158.60	33436.15
5.5	RCC in Roof Slab	12.18	Cum	9527.90	116049.82
6	Providing & fixing in position High yield deformed bars/ reinforcement confirming to Fe 500 grade of SAIL make with cutting, bending, binding, straightening, tying and placing in position, using binding wire 18 to 20 gauge, cost & conveyance of materials,labour, T &P etc. complete as per direction of the Engineer-in-charge.	43.64	Qtl	8201.40	357909.10
7	Providing Fly ash brick masonry in C.M.(1:6) with fly ash brick & PSC cement of approved quality and size including splays, cutting, circular moulding with cost & conveyance of materials, labour ,T&P, royalty, taxes, curing etc. complete as per direction of the Engineer-in-charge. <b>(i) In foundation &amp; Plinth</b>	50.12	Cum	4346.90	217866.63
	<b>(ii) Superstructure</b>	39.78	Cum	4380.20	174244.36
8	Providing 12mm thick cement plaster in c.m. (1:6) over brick work finished smooth with PSC cement including cost & conveyance of materials, labour, T&P, royalty, taxes, curing etc. complete as per direction of the Engineer-in-charge.	314.96	Sqm	136.60	43023.54
9	Providing 16mm thick C.P. in C.M.(1:6) over brick work finished smooth after racking out joints with using PSC cement & cost, conveyance of materials labour, T&P required for the work including royalty etc.complete as per direction of the Engineer-in-charge.	161.40	Sqm	194.60	31408.44
10	Providing 6mm thick C.P. in C.M.(1:4) to R.C.C surface including close deep chipping & slurry treatment with PSC cement & cost, conveyance of materials labour, T&P required for the work including royalty etc.complete as per direction of the Engineer-in- charge.	63.58	Sqm	153.40	9753.17
11	Providing 12mm thick plaster in c.m. (1:4) for skirting and dados using PSC cement including cost & conveyance of materials, labour, T&P, royalty, taxes, curing etc. complete as per direction of the Engineer-in-charge.	41.69	Sqm	157.40	6562.01
12	Supplying, fitting and fixing vetrified tile in floors of size 600mm x 600mm of approved make with application of polymer modified cement based water resistant adhesive bed of required thickness of 10mm and filling joints with epoxy grout of approved qualy including cost of all materials, labour T&P etc required for the work complete as per direction of the Engineer-in-Charge	101.88	Sqm	1008.40	102735.79
13	Providing & fixing Glazed Ceramic tiles (30cmx20cm) confirming to IS 13753 in walls, risers, dado, skirting treads on 12mm thick bed of cement mortar 1:3 (1cement : 3sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost & conveyance of materials,royalty labour, T &P etc. complete as per direction of the Engineer-in-charge.	125.35	Sqm	1122.50	140705.38

  
 M. Behar  
 Asst. Commr (M. Behar)  
 DRDA, Jaisore

BOA-02/02


14	Fixing Granite tiles (supplied) in walls, risers, dado, skirting on 12mm thick bed of cement mortar 1:3 (1cement : 3sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including cost & conveyance of materials, royalty, labour, T &P etc. complete as per direction of the Engineer-in-charge.	2.68	Sqm	2943.50	7888.58
15	Supplying, fitting & fixing dressed seasoned <b>Sal wood</b> work framed and fixed (wrought and put up) in trusses, purlin, frames of door, windows, ventilators & beams including tarring 1 coat to back.	0.51	Cum	51646.4	26339.66
16	Supplying & fixing <b>W.I. Clamps</b> 25cm to 30cm long of 35mm x 5 mm size for doors & windows and ventilators including fixing in cement concrete (1:3:6) with 12 mm to 20 mm hard stone chips or in cement mortar (1:3 ) including cost of materials.	60	Nos	11.3	678.00
17	Supply & fixing 32 mm thick <b>Plasal wood panel door / window shutter</b> with 20mm to 25mm thick panel plank complete with wooden hinged cleats etc. including all labour charges but excluding the cost of fittings.	18.29	Sqm	4282.6	78328.75
18	Providing & fixing M.S. Iron shutters for Doors/ Window made up of M.S angle frame, M.S Sheet, M.S flat including cost & conveyance of all materials,fitting, labour, T&P required for the work etc. complete as per direction of the Engineer-in-charge.	504.00	Kg	143.30	72223.20
19	Supply & fixing of <b>M.S. widow grill door &amp; grills</b> including cost of screws complete.including cost & conveyance of all materials,fitting, labour, T&P required for the work etc. complete as per direction of the Engineer-in-charge.	605.75	Kg	88.70	53730.03
20	Providing three coats of white washing with shell lime including necessary preparation of surface, cost & conveyance of materials, labour, T&P etc. complete as per direction of the Engineer-in-charge.	32.79	Sqm	15.70	514.80
21	Providing two coats of distemper of approved shade over one coat of primer on wall surface including cost, conveyance of materials labour, T&P etc.complete as per direction of the Engineer-in-charge.	261.01	Sqm	128.80	33618.09
22	Finishing wall surface of wall with cement base wall putty & finished smooth to receive pain tincluding cost, conveyance of materials labour, T&P etc.complete as per direction of the Engineer-in-charge.	261.01	Sqm	71.60	18688.32
23	Earth work in hard soil beyond initial lead & lift & carriage Earth by Mechanical Means including dressing, breaking clods to maximum 5cm to 7cm, laying in layers not exceeding 0.3 m in depth including sectioning, cambering & ordinary compaction of PRR & all labour ,T&P, royalty & taxes etc. complete as per direction of the Engineer-in-charge.	104.21	Cum	339.50	35379.30
24	Providing 2.5cm thick Damp proof course with P.C.C (1:2:4) using 12mm size h.g chips including cost & conveyance of materials, labour, T&P royalty taxex, curing etc. complete as per direction of the Engineer-in-charge.	17.03	Sqm	292.30	4977.87
25	Providing 20mm thick grading plaster ( 1:4) over the roof slab as grading plaster finished smooth using PSC cement including watering curing for specified period with cost conveyance, royalty & taxes of all materials, labour, T&P, scaffolding etc. complete as per specification & direction of Engineer-in-charge.	96.03	Sqm	217.20	20857.72

  
 A. Behar  
 17/01/2023  
 17/01/2023

BQ-02/03

26	2 coats of synthetic enamel paint on new / old steel surface with one coat primer in ground floor etc. complete as per direction of the Engineer-in-Charge.	38.67	Sqm	194.70	7529.05
27	2 coats of synthetic enamel paint on new / old wood surface with one coat primer in ground floor etc. complete as per direction of the Engineer-in-Charge.	47.19	Sqm	198.80	9381.37
28	S & F 4 mm plain glass with cost of nail , screw for ventilator including necessary preparation of surface, cost & conveyance of materials, labour, T&P etc. complete as per direction of the Engineer-in-charge.	1.49	Sqm	509.00	758.41
29	Providing two coats of water proofing cement paint including necessary preparation of surface, cost & conveyance of materials, labour, T&P etc. complete as per direction of the Engineer-in-charge.	224.97	Sqm	50.40	11338.49
30	Supply of 100 mm Mild steel butt hinges including necessary screws.	24.00	Nos	19.10	458.40
31	Supply of 250 mm x 16 mm Aluminium Sliding door bolt including necessary screws.	10.00	Nos	229.70	2297.00
32	Supply of 150 mm Aluminium handle with 175mm x 40 mm flat including necessary screws.	20.00	Nos	32.20	644.00
33	Supply of 150 mm x 10 mm Aluminium tower bolt including necessary screws.	10.00	Nos	52.80	528.00
34	Supply of 200 mm x 10 mm Aluminium tower bolt including necessary screws.	10.00	Nos	64.10	641.00
35	Moorum filling & consolidated with hand ramming etc. complete as directed by the Engineer in charge .	2.83		1003.40	2839.62
36	S&F masonry informatory sign board including painting, lettering as per drawing etc. complete as directed by the Engineer in charge .	1.00	Nos	6293.10	6293.10
				<b>Total : Rs.</b>	<b>1996714.61</b>
<b>Total : 36(Thirty Six items ) only</b>				<b>Say :- Rs.</b>	<b>1996715.00</b>

Signature of Contractor

  
Asst. Engineer (NHM), B.D.O. Jaleswar Block  
DRDA, Balasore

My/ our quoted rate is..... % Excess over / Less than / equal to the estimated cost.

(Rate to be quoted both figure & word)

Submission of Rs. 6,000 /- (Rupees Six Thousands ) Only, Vide Bank Draft No.

Dated. , Name of the Bank towards cost of the tender paper .

Signature of Contractor

  
B.D.O. , Jaleswar Block

BOR-02/04

**BILL OF QUANTITIES SI. No. -03**

**NAME OF THE WORK:- CONSTRUCTION OF HWC SC AT SYAMNAGAR SC UNDER JALESWAR BLOCK**


Tender Call Notice No  
 Approx. Estimated Cost :-Rs. 1913156.00  
 E.M.D. to be deposited :- Not Required  
 Cost of Tender Paper :- Rs. 6,000/-  
 Class of Contractor :- 'D' & 'C' Class  
 Last Date of Avail the tender Paper in Web site :- 24.10.2021  
 Last Date of receipt of tender :- 28.10.2021  
 Date of Opening of Tender :- 29.10.2021 at 11.30 A.M.  
 Time of Completion :- Four Months

Sl. No	Description of items	Unit	Quantity	Rate	Amount
1	Earthwork in excavationin of foundation in hard soil including rough dressing and levelling the bed etc complete	Cum	53.24	184.62	9828.95
2	Filling in foundation and Plinth with sand in well watered and compact including cost of all materials, loburs, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.	Cum	119.83	453.71	54370.28
3	P.C.C. (1:3:6) with nominal size stone aggregate, sand etc . including cost of all materials, loburs, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.	Cum	16.75	4664.17	78127.42
4	Cement concrete (1:2:4) with nominal size stone aggregate, sand etc . including cost of all materials, loburs, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.	Cum	3.76	6327.01	23789.55
5	Labour for cutting, bending, binding, shifting to site, tying and placing in position HYSD Bar etc. as per design including cost of all materials, loburs, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge. (G.F.)	qtl	51.69	8131.82	420334.03
	Reinforced Cement Concrete M20 with nominal size down graded 20mm size aggregate, sand etc with machine mix and hosting, laying and compacting with mechanical means including cost of all materials, loburs, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.				
6	Column Base in Foundation	Cum	17.65	5376.86	94877.97
7	Grade Beam	Cum	6.80	5739.06	39025.63
8	Column & Roof Beam	Cum	9.14	12517.77	114412.46
9	Lintel GF	Cum	3.03	8948.35	27113.50
10	Lintel FF	Cum	0.47	9770.32	4592.05
11	Chaja	Sqm	7.62	813.69	6200.33
12	Roof slab	Cum	13.00	9533.32	123933.12
13	Staircase	Cum	1.92	10570.18	20294.75

  
**Asst. Engineer (NHM)**  
**DRDA, Balasore**

BOQ-03/01

14	20mm thick cement plaster over roof slab with C.M(1:4) including cost of all materials, labours, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.	sqm	92.56	215.39	19936.18
15	Fly ash Brick work (1:6) in foundation including cost of all materials, labours, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.	cum	20.38	4411.76	89911.64
16	Fly ash Brick work (1:6) in superstructure including cost of all materials, labours, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.	Cum	42.88	4445.09	190605.39
17	Fly ash Brick work (1:6) in 1st floor including cost of all materials, labours, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.	Cum	11.54	4687.77	54100.33
18	6mm thick cement plaster in C.M (1:4) including cost of all materials, labours, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.	Cum	14.68	152.06	2232.21
19	16mm thick cement plaster in C.M (1:6) including cost of all materials, labours, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.	sqm	368.60	194.42	71662.81
20	16mm thick cement plaster in C.M (1:6) including cost of all materials, labours, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.	sqm	29.99	198.90	5965.06
21	12mm thick cement plaster in C.M (1:6) including cost of all materials, labours, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge. (Ground Floor)	sqm	195.89	136.45	26729.79
22	12mm thick cement plaster in C.M (1:6) including cost of all materials, labours, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge. ( First Floor)	sqm	94.06	141.49	13308.09
23	Fixing vetrified tiles in dados,skirting and riser of steps on 12 mm thick cement plaster 1:3 jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of precast tiles,all materials,labour,t&p,all taxes of materials etc complete.	sqm	85.21	954.55	81335.24
24	Providing & laying granite slab over prepared baseincluding cost of all materials, labours, transportation , T&P and all taxes in all respect in complete with all respect as per direction of Engineer-in-Charge.	sqm	5.64	1667.40	9396.32
25	Fixing Ceramic tiles in dados,skirting and riser of steps on 12 mm thick cement plaster 1:3 jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of precast tiles,all materials,labour,t&p,all taxes of materials etc complete.	sqm	7.97	706.69	5629.64

  
 Anil Engineer (NHM)  
 DRDA, Balasore

BOA-03/02

26	Supplying Fitting and Fixing Chequerrd Tiles in Floors in Cement Mortar (1:4) including cost of all materials, loburs, transportation , T&P and all taxes in all respect In complete with all respect as per direction of Engineer-in-Charge.	sqm	18.43	489.04	9015.19
27	Supplying and fitting and fixing of M.S shutter of approved design including all labour and material etc complete.	Qntl	19.01	7472.68	142071.41
28	Painting 2 coats over 1-coat of primer including all labour and material etc complete.	sqm	76.03	186.40	14171.16
29	Distempering 2 coats to wall distemper of approved shade with a coat of primer etc complete.(GF)	sqm	480.97	120.56	57987.38
30	Distempering 2 coats to wall distemper of approved shade with a coat of primer etc complete.(FF)	sqm	29.99	121.96	3657.19
31	Wall painting 2 coat with Weather coat of approved shade to give an even shade including cost of paint.	sqm	195.89	128.31	25134.33
32	Finishing walls with weather paint of approved shade on new work two coats over one coat of cement wash to give an even shade including cost of cement paint, 1st floor	sqm	94.06	130.72	12296.08
33	Providing ,fitting and fixing transparent corrugated Fibre Sheet in roof including cost of sheets, labour for fixing of ridges ,wind ties including drilling holes in wind ties, etc complete , but excluding cost of ridges,wind ties, and .fittings	sqm	15.79	1144.14	18066.01
34	Branding for HWC as per specification in outer plaster surface including all complete	Sqft	340.86	45.00	15338.88
35	Supplying fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia. Of 2mm thick circular pipe with balustrade of size 32mmx32mmx2mm @ 0.90mtr C/C and stainless square pipe of size 32mmx32mmx2mm in 3 rows in staircase as per approved design and specification etc all completed.	Rmtr	7.93	3495.14	27705.35
				Rs.	1913155.73
<b>TOTAL 35 (Thirty Five ) Items only</b>				<b>Say Rs.</b>	<b>1913156.00</b>

Signature of Contractor

Asst. Engineer (NHM),  
DRDA, Balasore

B.D.O. Jaleswar Block

My/ our quoted rate is..... % Excess over / Less than / equal  
to the estimated cost.

(Rate to be quoted both figure & word)

Submission of Rs. 6,000 /- (Rupees Six Thousands ) Only, Vide Bank Draft No.

Dated. , Name of the Bank

towards cost of the tender paper .

Signature of Contractor

B.D.O. Jaleswar Block

BOA-03/03